



The Coro
County Square
Ulverston
Cumbria
LA12 7LZ

hello@thecoro.co.uk
www.thecoro.co.uk
01229 588994

Main Hall Tech Specs 2022

Contact

Head of Site and Technical
Casi Clark
casi.clark@ulverstonenterprises.uk

Parking

We have space for 2 cars and 1 van. There are 2 car parks within 2 minutes walk and plenty of on-street parking available. Please contact if you require larger vehicle parking so we can get the proper permits to park behind the building.

Tech Position

Main Hall Tech Booth is at the Back of House Right for Lights, Sound and Stage Manager. There is also a Stage Manager position SL with 4 camera views.

Lighting

House plot, as is, is covered with Main Hall charge. FOH fixed positions. If a rehang is required onstage there is an additional charge for pre-rig. Lighting bars are noted on grid list. We have limited gels and breakaways. Please inquire for current house plot.

Lighting Desk

ETC Ion
Version 2.9,2 Build 8
Fixture Library Version 2.9.2.23

Dimmers

72 x 1k Beta Pack 2
6 circuits on relays

Fresnels

16-1k

Pars

16-1k

Floods

- 5-1k Nocturns
- 4- 1/2k CCT

Profiles

- 5- 1k Cantata
- 6- 1k Source 4

LEDS

- 7- LEDJ ALU Quad Par 64
- 3- Chauvet Color Dash Par Hex 12

Moving Heads

- 5- Elation Platinum Spots
- 4- Chauvet Rogue R1

Follow Spots (need advance notice)

- 2- Super Kerrigan 1200w

Effects

Hazer

- 1- Le Maitre Neutron XS

Temporary Power Supply

Lighting

- 125 amp three phase (c form or tails)
- Or
- 63 amp three phase plus power supply for movers and LED fixtures

Sound

- 63 amp single phase
- 13 amp twin socket (stage left)

Sound

Sound Console

- Midas M32
- Firmware V 4.06

Speakers

- 2- EV Stage 200's paired Mains (fixed)
- 2- EV Stage 200's paired Balcony (Fixed)
- 8- Bose in ceiling Under Balcony speakers
- 2- RCF Subwoofers
- 2- RCF Infill Front Fills
- 2- Powered Stage Monitors

1- Powered Speaker

Microphones

4- WA wireless Handheld/Lav mics
4- AT Rifle mics
4- Shure SM58
2- Shure 57
2- PZM floor mics

DI Box

1-Dual

Com

3- Tec Pro (2 - tech booth, 1-SL SM station)

Video

1- Front Projection H: 2.86m/9'5" W:5.7m/16'8"
1- Rear Projection 2.86m/9'5" W:5.7m/16'8" (need advance notice)
1- Sanyo PLC-XP46 4,100 Lumens

Stage

Stage is raked 1:20

The main floor to stage height is 1.25m/4'1". There are stairs to the house left and right of the stage. Equipment needs to be manually lifted to the stage

Proscenium arch width: 8.7m/28'5"

Proscenium arch height: 4.8m/15'7"

Stage Depth: 8.4m/27'5"

Flying height

Downstage 7m/22'9"

Upstage 6.8m/22'3"

20 bars

Please see grid list for specifics

Grid system

ASM Spider Winch

Controls

Stage Left and Stage Right

Maximum Load

315 kg/694 pounds per bar

Curtain tracks (need advance notice)

4-Swipes tracks

1- Overlap

Drapes**Main Tabs**

Red Velvet hand operated Stage Left

Full stage black:

8 sectioned with Velcro

Legs

2- pairs Black

Safety Curtain

Curtain track must be clear at all times

Dressing Rooms

Access Stage Right: very steep stairs

Access Stage Left: very steep stairs and chair lift

4 large and 1 small rooms under stage

Galley kitchen

2 - restrooms with toilets and shower

Other

Please inquire about decking for additional charge