

The Coro
County Square Ulverston
Cumbria
LA12 7LZ
hello@thecoro.co.uk
thecoro.co.uk
01229 588994

# Main Hall Tech specs 2022

Contact
Head of Site and Technical
Gary Sharpe
<a href="mailto:sharpegaz@me.com">sharpegaz@me.com</a>

## Parking

We have space for 2 cars and 1 van. There are 2 car parks within 2 minutes walk and plenty of on-street parking available. Please contact if you require larger vehicle parking so we can get the proper permits to park behind the building.

## **Tech Position**

Main Hall Tech Booth is at the Back of House Right for Lights, Sound and Stage Manager. There is also a Stage Manager position SL with 4 camera views.

# Lighting

House plot, as is, is covered with Main Hall charge. FOH fixed positions. If a rehang is required onstage there is an additional charge for pre-rig. Lighting bars are noted on grid list. We have limited gels and breakaways. Please inquire for current house plot.

# Lighting Desk

ETC Ion

Version 2.9,2 Build 8

Fixture Library Version 2.9.2.23

## **Dimmers**

72 x 1k Beta Pack 2 6 circuits on relays

## Fresnels

16-1k

Pars

16-1k

Floods

5-1k Nocturns

#### **Profiles**

- 5- 1k Cantata
- 6- 1k Source 4

## **LEDS**

- 7- LEDJ ALU Quad Par 64
- 3- Chauvet Color Dash Par Hex 12

## Moving Heads

- 5- Elation Platinum Spots
- 4- Chauvet Rogue RI

## Follow Spots (need advance notice)

2- Super Kerrigan 1200w

## **Effects**

## Hazer

1- Le Maitre Neutron XS

# Temporary Power Supply Lighting 125 amp three phase (c form or tails)

Or

63 amp three phase plus power supply for movers and LED fixtures

## Sound

63 amp single phase

13 amp twin socket (stage left)

#### Sound

## Sound Console

Midas M32

Firmware V 4.06

# Speakers

- 2- EV Stage 200's paired Mains (fixed)
- 2- EV Stage 200's paired Balcony (Fixed)
- 8- Bose in ceiling Under Balcony speakers
- 2- RCF Subwoofers
- 2- RCF Infill Front Fills

- 2- Powered Stage Monitors
- 1- Powered Speaker

# Microphones

- 4- WA wireless Handheld/Lav mics
- 4- AT Rifle mics
- 4- Shure SM58
- 2- Shure 57
- 2- PZM floor mics

#### DI Box

I-Dual

#### Com

3- Tec Pro (2 - tech booth, I-SL SM station)

#### Video

- 1- Front Projection H: 2.86m/9'5" W:5.7m/16'8"
- 1- Rear Projection 2.86m/9'5" W:5.7m/16'8" (need advance notice)
- 1- Sanyo PLC-XP46 4,100 Lumens

# Stage

Stage is raked 1:20

The main floor to stage height is 1.25m/4'1". There are stairs to the house left and right of the stage. Equipment needs to be manually lifted to the stage

Proscenium arch width: 8.7m/28'5"

Proscenium arch height: 4.8m/15'7

Stage Depth: 8.4m/27'5"

Flying height

Downstage 7m/22"9"

Upstage 6.8m/22'3"

20 bars

Please see grid list for specifics

Grid system

**ASM Spider Winch** 

Controls
Stage Left and Stage Right
Maximum Load
315 kg/694 pounds per bar

Curtain tracks (need advance notice)
4-Swipes tracks
1- Overlap

Drapes
Main Tabs
Red Velvet hand operated Stage Left

Full stage black: 8 sectioned with Velcro

Legs 2- pairs Black

Safety Curtain Curtain track must be clear at all times

**Dressing Rooms** 

Access Stage Right: very steep stairs

Access Stage Left: very steep stairs and chair lift

4 large and 1 small rooms under stage Galley kitchen 2 - restrooms with toilets and shower

Other

Please inquire about decking for additional charge